

**UNDERGROUND INJECTION CONTROL
PERMIT APPLICATION**

Ute Tribal # 31-07
1976' FNL & 2168' FEL
Sec. 31, T5S-R3W
Duchesne County, Utah
API # 43-013-32036

July 2015

Prepared for:
Bruce Suchomel
Groundwater Program, Mail Code 8P-W-UIC
U.S. Environmental Protection Agency
1595 Wynkoop St
Denver, CO 80202-1129

Prepared by:
Petroglyph Energy, INC.
960 Broadway Avenue, Suite 500, P.O. Box 70019
Boise, Idaho 83707
(208) 685-7600
FAX (208) 685-7605

TIER 1

- CBL - headwater
unreadable/low
- CBL can't read stages
or assess confining
- no summary report
NO CBL FOR LOG.
- DEVIATION LOG
- depth to USDW from
31-07 what source

UNDERGROUND INJECTION CONTROL PERMIT APPLICATION

Ute Tribal # 31-07

1976' FNL & 2168' FEL

Sec. 31, T5S-R3W

Duchesne County, Utah

API # 43-013-32036

July 2015

Prepared for:

Bruce Suchomel

Groundwater Program, Mail Code 8P-W-UIC

U.S. Environmental Protection Agency

1595 Wynkoop St

Denver, CO 80202-1129

Prepared by:

Petroglyph Energy, INC.

960 Broadway Avenue, Suite 500, P.O. Box 70019

Boise, Idaho 83707

(208) 685-7600

FAX (208) 685-7605

LIST OF ATTACHMENTS

Attachment No. 1	Area Topography Map
Attachment No. 2	Site Map
Attachment No. 3	Map of the A-Marker surface
Attachment No. 4	Cross-Sections of the injection formation
Attachment No. 5	Water Analysis
Attachment No. 6	Completion data for all wells in the AOR
Attachment No. 7	CBL for the UIC well
Attachment No. 8	Open hole log for the UIC well
Attachment No. 9	List of owners and Affidavit Notification
Attachment No. 10	Well bore diagrams for the UIC well
Attachment No. 11	P&A procedure
Attachment No. 12	MIT procedure
Attachment No. 13	Surety Bond letter

**SUMMARY DOCUMENT
UIC WELL APPLICATION
Ute Tribal 31-07
API # 43-013-32036**

The following document contains information provided in support of the application for the conversion of the Ute Tribal 31-07 well to an injection well in the Green River formation in the Antelope Creek Field in Duchesne County, Utah.

The Antelope Creek Field falls within the Uintah and Ouray Indian reservations and is within Indian Country; therefore, for facilities located on the reservation, only EPA-issued UIC permits are necessary for compliance with UIC regulations.

The EPA has issued an Area Permit #UT20736-00000 for the Underground Injection Control for the Antelope Creek Field. This area permit allows for additional producing wells to be converted to injection wells for enhanced recovery.

- (1) Petroglyph Energy, Inc. (Petroglyph) is the operator and only working interest owner of wells located in the Antelope creek Field, Duchesne County, Utah. Petroglyph's business address is provided below:

Petroglyph Energy, Inc.
960 Broadway Avenue, Suite 500
P.O. Box 70019
Boise, ID 83707

- (2) Enclosed as Attachment No. 1 is a topographic map of a portion of the Antelope Creek Field, identifying all wells located in this area. The legal location for the Ute Tribal 31-07 is 1976' FNL & 2168' FEL SW/NE Sec. 31, T5S-R3W.
- (3) Attachment No. 2 is a map of the well. This map shows a circle with a ¼ mile radius centered on the Ute Tribal 31-07 well. The ¼ mile radius encompasses the area of review, AOR, within which Petroglyph is required to investigate all wells for mechanical integrity. The ¼ mile radius also identifies mineral ownership; all lands within the AOR are leased to Petroglyph by the Ute Tribe as indicated by yellow shading. The AOR has Ute Tribal 31-06 well(s) located in its ¼ mile radius.

- (4) Petroglyph proposes to utilize the Ute Tribal 31-07 as an injection well for enhanced recovery in the Antelope Creek Field.
- (5) Injection Zone – The injection intervals are between 3982' and 5954' True Vertical Depth and located in the lower portion of the Green River Formation. The injection zone is confined within a 1972' section between the Green River "A" Lime marker bed and the top of the Basal Carbonate in the lower part of the formation. The injection zone is composed of lenticular calcareous sandstones interbedded with low permeable carbonates and calcareous shales. The lenticular sandstones vary in thickness from 1 to 30 feet.

Confining Zone – The overall confining strata above the injection zone consists of impermeable Green River calcareous shales and continuous beds of microcrystalline dolostone. The confining zone in the Ute Tribal 31-07 is 217 feet thick.

Attachment No. 3 is a structure map of the A-Marker surface.

Attachment No. 4 is a cross-section of the injection interval and confining zone.

- (6) Enclosed as Attachment No. 5 are standard analyses of produced water from three batteries that currently serve as central handling facilities for all project producing wells. The analysis of the Green River formation water from the Ute Tribal 18-08 Satellite Battery is 12805 mg/L of total dissolved solids (TDS), Ute Tribal 21-11 Satellite Battery is 15659 mg/L TDS, and Ute Tribal 34-12-D3 Satellite Battery is 14590 mg/L TDS.

Injectate in the field is a mixture of produced water and fresh make-up water. The nearest injection well is the Ute Tribal 30-15, the most recent analysis of the water being injected into the Green River formation at this location is 10160 mg/L TDS. This analysis is also included in Attachment No. 5.

- (7) A summary of completion data from the Ute Tribal 31-07 and offset wells in the AOR are included in Attachment No. 6
- (8) The cement bond log is included in Attachment No. 7.
- (9) The open hole log for the Ute Tribal 31-07 is included in Attachment No. 8.

(10) The Antelope Creek Field is operated under a Cooperative Plan of Development between the Ute Tribe and Petroglyph Energy. At the Ute Tribal 31-07 location, all mineral owners, surface owners and operators located within the AOR ¼ mile radius have been notified of the submitted EPA application to convert to injection. Attachment No. 9 is the Affidavit of Notification to all owners.

(11) Petroglyph requests a maximum surface injection pressure of **1802psi**. The EPA Area Permit No. UT20736-00000 uses the formula:

$$P_m = (0.88\text{psi/ft} - 0.43\text{psi/ft}(S_g)) D$$

Where:

P_m = Maximum surface injection pressure

0.88psi/ft = Fracture gradient

D = Top perforation depth

0.43psi/ft = Hydrostatic pressure/hydraulic head

S_g = Specific gravity of injection fluid

For the Ute Tribal 31-07:

$$\mathbf{1802\text{psi} = (0.88\text{psi/ft} - 0.43(1.00)) 4004\text{ft}}$$

(12) Three wellbore diagrams for the Ute Tribal 31-07 are in Attachment No. 10. One diagram is for production, one for injection, and one for Plug & Abandonment (P&A).

(13) The P&A procedure for this well is shown in Attachment No. 11.

(14) Once the draft permit is issued, Petroglyph will conduct a Mechanical Integrity Test and a static bottom-hole pressure test. The MIT procedure is contained in Attachment No. 12. The conversion work will be satisfactorily completed and submitted to the EPA on Form 7520-12. A wellbore schematic will be included with this form.

- (15) Petroglyph will give proof of financial responsibility by posting a surety bond for the UIC well prior to final permit approval. A copy of this letter is contained in Attachment No. 13.
- (16) Petroglyph will install various gauges on the well so that the injection pressure and tubing/casing annulus pressure can be monitored. The well will be equipped with a flow meter with a cumulative volume recorder.

Permit No: UT2

Well: UT 31-07

What Needs to be Done	Information Sources	Review & Evaluation Notes
Determine name, top and base of the confining zone(s) and the injection zone(s).	<input type="checkbox"/> Geologic data submitted <input type="checkbox"/> Well logs from area <input type="checkbox"/> Published articles	Conf Zone: top <u>3763</u> base <u>3982</u> Inj Zone: top <u>3982</u> base <u>5954</u> (<u>Garden Gulch 2-Marker</u>) (<u>top Wasatch</u>)
Determine name, top and base of all USDWs. List base of lowermost USDW: Determine which USDWs are actually being used for water supply.	<input type="checkbox"/> Geologic data submitted <input type="checkbox"/> nearby Water analyses <input type="checkbox"/> nearby Well logs <input type="checkbox"/> Water supply wells <input type="checkbox"/> Published articles	Surface Elevation: <u>GL: 6793 KB: 6803</u> Pub #92 base USDW: bgs: elev: submitted base USDW bgs: <u>1803</u> elev: base of Uinta / top Green River: <u>1510'</u> <u>USDW in Green River</u>
Review and evaluate construction, casing and cementing records of proposed well.	<input type="checkbox"/> Data submitted <input type="checkbox"/> Completion/workover reports <input type="checkbox"/> Contractor invoices <input type="checkbox"/> Logs: CBL, RTS, Temp, casing inspection, etc.	TD: <u>6063</u> PBTD: <u>5925</u> surface csg <u>8 5/8" 24#</u> ft <u>0-276</u> s: long strg csg <u>5 1/2" 15.5#</u> ft <u>0-5998</u> s: TOC: submitted: <u>850</u> CBL: <u>860</u> Wells in AOR: TD TOC <u>31-06 deviated 6377 Surf</u>
Review and evaluate construction, casing and cementing records of AOR wells that penetrate injection zone.	72/1	
Review P&A plan for effective USDW protection, injection zone isolation and well closure.	<input type="checkbox"/> P&A plan <input type="checkbox"/> Area geology	plug depths:
Review amount of FR - is it adequate to cover P&A costs of proposed in P&A plan?	<input type="checkbox"/> contractor bids / P&A cost histories <input type="checkbox"/> nearby well P&A costs	FR instrument: Amount: \$
Calculate the maximum allowable injection pressure (MAIP).	<input type="checkbox"/> Fracture treatments <input type="checkbox"/> Step Rate Test results <input type="checkbox"/> Fracture gradient	top perforation: bottom perforation: injectate specific gravity: <u>1.01</u> Frac Gradient: <u>.88</u> p: initial MAIP = <u>1760</u> psi
Determine which logs and tests will be performed.		

Cement Bond Index (in millivolts - mV)

Date: September 2, 2015

Operator: Petroglyph

Well: Ute Tribal 31-07

Permit : _____

Enter the following values:

Amplitude at 0% Bond (A-0) (in mV) = 72 mV

Amplitude at 100% Bond (A-100) (in mV) = 1 mV

Amplitude at 80% Bond (A-80) = 2.4 mV

$$[(0.2)\log A_0 + (0.8)\log A_{100}]$$

*Can't read
postage on log*

Amplitude at 90% Bond (A-90) = 1.5 mV

$$[(0.1)\log A_0 + (0.9)\log A_{100}]$$

Amplitude at 70% Bond (A-70) = 3.6 mV

$$[(0.3)\log A_0 + (0.7)\log A_{100}]$$

Amplitude at 60% Bond (A-60) = 5.5 mV

$$[(0.4)\log A_0 + (0.6)\log A_{100}]$$

Maximum Allowable Injection Pressure (MAIP)
From Fracture Gradient

Date: 09/02/2015 Operator: Petroglyph
Well: Ute Tribal 31-07
Permit #: _____

Enter the following values:

Specific Gravity of injectate =	<u>1.010</u>	g/cc
Depth to top of injection interval =	<u>3,982</u>	feet
Fracture Gradient (F G) =	<u>0.880</u>	psi/ft

MAIP = **1,760** psig

(rounded down to nearest 5 psig)

where:

$$MSIP = [FG - (0.433 * SG)] * \text{Depth to top of injection interval} = 1762.712$$

Well Completion Data
Ute Tribal 31-07

Well	Surface Casing				Production Casing			
	Size (inches)	Depth (ft KB)	Cement Amount (sx)	Cement Top	Size (inches)	Depth (ft KB)	Cement Amount (sx)	Estimated Cement Top
Ute Tribal 31-07	8-5/8	276	165	surface	5-1/2	5998	590	850
Ute Tribal 31-06	8-5/8	538	360	surface	5-1/2	6377	840	surface

Ute Tribal 31-07 Well History

Well History:

Spud Well: 2/25/1998
 Completed: 4/16/1998
 First Production: 4/22/1998

Tops (KB):

BMSW* Found at 1803'
 Green River 1510'
 A Marker 3982'
 X Marker 4468'
 Douglas Creek 4605'
 B Limestone 4980'
 Castle Peak 5460'
 Basal Carbonate 5954'

Perf History

4/9/1998

B02	4028' to 4034'
B08.1	4310' to 4314'
B10	4378' to 4382'
C05	4658' to 4662'
C08.1	4870' to 4874'
C09.2	4933' to 4937'
D01	4998' to 5002'

GL: 6793'

KB: 6803'

8 5/8" 24# Surface CSG @ 276' KB
 cmt'd w/165sx

Surface Hole size 12 1/4"

Cement top @ 850'

5 1/2" 15.5# J-55 CSG @ 5998'
 cmt'd w/590 sx

Hole Size 7 7/8" bit

Perf's:

B02 4028' to 4034'
 B08.1 4310' to 4314'
 B10 4378' to 4382'
 C05 4658' to 4662'
 C08.1 4870' to 4874'
 C09.2 4933' to 4937'
 D01 4998' to 5002'

Petroglyph Operating Co., Inc.
 Ute Tribal #31-07
 (1976' FNL & 2168' FEL)
 SW NE Section 31, 5S- 3W
 Antelope Creek Field
 Duchesne Co. Utah
 API#: 43013320360000

*Plate 1 Utah Geological Survey Special Study 144.
 (2012). BMSW Elevation Contour Map, Uinta Basin,
 Utah. [map]. (CA 1:200,000)

PBTD @ 5925' KB

TD @ 6063' KB

(Not to Scale)

Ute Tribal 31-07 Injection

Well History:

Spud Well: 2/25/1998
Completed: 4/16/1998
First Production: 4/22/1998

Tops (KB):

BMSW* Found at 1803'

Green River 1510'

A Marker 3982'

X Marker 4468'


Douglas Creek 4605'

B Limestone 4980'

Castle Peak 5460'

Basal Carbonate 5954'

Injection packer @ 3914'



GL: 6793'

KB: 6803'

8 5/8" 24# Surface CSG @ 276' KB

cmt'd w/165sx

Surface Hole size 12 1/4"

Cement top @ 850'

5 1/2" 15.5# J-55 CSG @ 5998'

cmt'd w/590 sx

Tubing 2 7/8" 6.5# J55

Hole Size 7 7/8" bit

Perf's:

Add B01 4004' to 4010'

B02 4028' to 4034'

B08.1 4310' to 4314'

B10 4378' to 4382'

C05 4658' to 4662'

C08.1 4870' to 4874'

C09.2 4933' to 4937'

Add D01 4996' to 4998'

D01 4998' to 5002'

Add D01 5002' to 5008'

Add D3 5054' to 5058' and 5062' to 5071'

Add E01.1 5536' to 5540'

Add E03.3 5656' to 5658' and 5664' to 5666'

PBTD @ 5925' KB

TD @ 6063' KB

Petroglyph Operating Co., Inc.

Ute Tribal #31-07

(1976' FNL & 2168' FEL)

SW NE Section 31, 5S- 3W

Antelope Creek Field


Duchesne Co. Utah

API#: 43013320360000

*Plate 1 Utah Geological Survey Special Study 144. (2012).
BMSW Elevation Contour Map, Uinta Basin, Utah. [map]. (CA
1:200,000)

(Not to Scale)


Ute Tribal 31-07 Plug and Abandonment





ATTACHMENT NO. 1: AREA MAP

1:12000

500 0 500 1000 ft
1 inch = 1000 feet



ATTACHMENT NO. 3: Map of the "A" Lime Marker



- Producing Oil Well
- Injection Well
- Injection Well, waiting on water
- PTPI
- D & A
- Waiting on Completion
- TA
- Shut In
- Injector Shut In
- P & A
- Shut In Gas Well

ANTELOPE CREEK
 DUCHESNE COUNTY, UTAH

Structure Map of the "A" Lime Marker
(approximate top of Injection Zone)
in the Vicinity of the
Ute Tribal 31-07
With Line of Cross Section A to A'

Hack 7-11-06
 Revised by
 JG 10-7-14

Petroglyph Energy, Inc. 555 S. Cox Rd. Bldg. 10 83709
 ©2014 GeoLink Regional, CT/31-07 structure map.gps

Structural Cross Section A to A' in the Vicinity of Ute Tribal 31-07

